BRUHATH BENGALURU MAHANAGARA PALIKE
Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64
No:EE/YNK-D/E-PMT/04/2014-15 Dated: 31-10-2014

APPROVED TENDER SCHEDULE –'B'

Item No: 13

Name of Work:-Improvements to roads and drains at KHB Colony and Nehru nagara in ward No- 01 of yelahanka Sub division.

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri .Y N RANGANATH	
				Rate	Rate in Words
1	KSRRB 300-1. Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications. MORTH chapter 3. No. 138/ Item No. 19.1/ PWD SR 2014-15	Cum	48.00	76.00	Rupees seventy six only
2	KSRB 100-1 Loading and unloading ofstone aggregates / sand/ kanker/ Moorum /soil KSRRB M100-1 Placing tipper at loading with front end loader dumpting turning for return trip excluding time for haulged and return trip complete as per specification item No 17.1 page 130 and KSRB M.100.4.1 costof haulage excluding loading and unloading MORTH to a distance of 4.00 K.M (Item No 17.4 Page 130 (SR 2014-15)	Cum	48.00	79.00	Rupees seventy nine only
3	KSRB 5-14 : Providing and constructing precast concrete solid blocks with compressive strength not les than 35 Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x20x20 cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. Page No.25 item No 5.27 SR 2014-15	Sqm	178.00	980.00	Rupees nine hundred eighty only
4	KSRB 4.2.2 : Providing and laying in position plain cement concrete of mix M20 withOPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @0.460cum with superplastesisre @ 3lts conforming to IS9103-1999Reffirmed machine mixed exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls(any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour HOM of machinery, curing, complete as per specifications. Specification. No. KBS 4.1,4.6, No. KBS 4.1,4.6, No. 13/ Item No. 4.11/ PWD SR 2014-15	Cum	14.50	6000.00	Rupees six thousand only

For Bruhat Bangalore Mahanagara Palike
Posted on 29-10-2014 12:16

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri .Y N RANGANATH	
				Rate	Rate in Words
5	KSRB 15.3.4 Providing 15m thick cement plaster in single coat with cement mortar 1:3,to brick masonry including rounding off corners wherever reuired smooth rendering, Providing and removing scaffolding, including cost of materials, labour. Curing complete as per specifications. Page No. 109 Item No 15.12 SR 2014-15	Sqm	356.00	190.00	Rupees one hundred ninety only
6	RCC Precast covering slab for drain (10cm thick)	Sqm	267.00	1490.00	Rupees one thousand four hundred ninety only
7	KSRRB 500-2: Cleaning the existing black topped surface with brooms, soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries complete as per specifications. MORTH chapter 5. No 157 item No 21.2 SR 2014-15	Sqm	3040.00	3.00	Rupees three only
8	SRRB M400-17: Providing, laying spreading and compacting graded stones aggregate to wet mix macadam specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying, in uniform layers with paver in sub base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH specification NO. 406, No. 154, item No 20.18 SR 2014-15	Cum	58.50	1430.00	Rupees one thousand four hundred thirty only
9	KSRRB M500-6: providing and applying primer coat with S.S bitumen emulsion on prepared surface of granular base such as WBM, WMM including clearing of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per specifications. MORTH specification NO. 502, No. 157 item No 21.6 SR 2014-15	Sqm	460.00	35.00	Rupees thirty five only
10	KSRRB 500-11: Providing and laying bituminous macadam on prepared surface with crushed coarse aggregates as per design mix formula for base / binding course including loading of aggregates with F.E. loader, hot mixing of stone aggregates and bitumen in hot mix plant 40 tonne capacity, transporting the mixed material in tipper to paver and laying mixed materials with paver finisher to the required level and grade, rolling by power roller to achieve the desired density, 50 / 75mm compacted thickness with 3.3% bitumen but excluding cost of primer / tack cost with lead upto 1km including cost of all materials, labour, HOM of machineries complete as per specifications. MORTH chapter 5, using 40/60 TPH capacity HMP with Mechanical Paver Gr -I (80 mm to 100mm) with 3.1% VG-30 Bitumen No. 158/ Item No. 21.11.5/ PWD SR 2014-15	Cum	29.25	6600.00	Rupees six thousand six hundred only
11	KSRRB 500-7: providing and applying tack coatusing 80/100 grade bitumen (VG10) on the prepared black topped surfaces at 2.5kg per 10 sqm, heating bitumen in boiler fitted with spray set (excluding clearing of road surface) including cost of all materials, labour, HOM of machinerics complete as per specifications. MORTH chapter 5, No. 157/ Item No. 21.7/ SR 2014-15	Sqm	3040.00	18.00	Rupees eighteen only

BBMP, Bangalore-560 092.

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri .Y N RANGANATH	
				Rate	Rate in Words
12	KSRRB M500-18: providing and laying Semidence bituminous concrete using crushed aggregates of specified grading, premixed with bituminous binder filler, transporting the hot mix to work site, laying with hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem roller to achieve the desire compaction as per MORTH specification clause No. 508 using 40-60 TPH capacity HMP with mechanical paver grading II (25-30mm) with 5% CRMB -55 grade, No. 160/ Item No. 21.21.6 SR 2014-15	Cum	76.00	10600.00	Rupees ten thousand six hundred only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.